In partnership with GMCA's GNUTION Project Is a standard of the stan

Living Lab Virtual Tour 12:40 - 13:00

Living Lab Launch Event 13:00 - 14:30

17 June 2021

Join us online! Register here







BIODIVERSITY





Elements Design 2 University of Salford MANCHESTER GREATER MANCHESTER European Union

UIA

QRain Garden

This innovative Rain Garden introduces a Sustainable Urban Drainage System (SuDS) that works as a sequence of passive water management practices, control structures and strategies designed to efficiently and sustainably drain surface water from the adjacent building roof with special regard for engaging biodiversity in the solutions. The water from the roof of Clifford Whitworth library is channeled through solutions in the building wall and ground water treatment solutions in the ground. This aims to minimise or even eliminate the water ending up in the university's surface water drainage network which flows into the nearby River Irwell.

> This green wall consists of 4 different planted sections: biodiversity, seasonal, pollinator, edible. This mass of plant life and soil helps insulate the building, utilize excess rainwater from the university campus, and attract more biodiversity to

In front of the green wall, and at the heart of the living lab sit two underground water tanks, which act as the collection point of excess water, as well as the base of automatic irrigation for the living lab system. The irrigation system in the living lab is automated to use the data from water monitors to identify if a certain element needs more water, pumping this





The roof area is split into 7 zones: sedum, wildflowers, perennials/meadow, brown roof, a lightweight tree pit, a climber wall and a living wall. The roof also includes 6 experimental beds for green roof design research purposes.

This all sits on a multilayered floor with a drainage underlayer that collates the

excess water from the roof and directs it to the central irrigation tank. All zones are monitored and are automatically watered as needed from the irrigation tank. The weight and retrofit considerations were an essential factor in the design of this roof.